

15-065-19015-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Location as "NE/CNWxSWx" or footage from lines Graham County. Sec. 20 Twp. 8 Rge. 23 (E) W (W)  
 Lease Owner Leo J. Dreiling Oil Co.  
 Lease Name Higer Well No. A-1  
 Office Address Victoria, Ks.  
 Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
 Date well completed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging filed \_\_\_\_\_ Oct. 8, 1964  
 Application for plugging approved \_\_\_\_\_ Oct. 12, 1964  
 Plugging commenced \_\_\_\_\_ Oct. 27, 1964  
 Plugging completed \_\_\_\_\_ Oct. 28, 1964  
 Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3760 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	185'	None
				5 1/2	3755'	2097'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand from 3745' to 3685'. Mixed and dumped 5 sx. of cement from 3685' to 3645'. Pulled casing to 450'. Mixed and circulated 8 sx. of gel mud. Mixed and pumped in 20 sx. of cement from 450' to 390'. Pulled casing to 180'. Mixed and pumped in 20 sx. of cement from 180' to 120'. Pulled rest of casing. Bailed off gel mud to 40'. Set 10' rock bridge from 40' to 30'. Mixed and dumped 10 sx. of cement from 30' to base of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 12 1964

CONSERVATION DIVISION  
Wichita, Kansas

11/12/64

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.  
 Address Box 304 Great Bend, Ks.

STATE OF Kansas COUNTY OF Ellis, ss.  
Leo J. Dreiling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo J. Dreiling  
Victoria, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9<sup>th</sup> day of November, 1964

My commission expires June 10, 1965 Notary Public.

15-065-19015-00-00

R

OPERATOR: Leo J. Dreiling  
Victoria, Kansas

CONTRACTOR: Mast Drilling, Inc.  
Russell, Kansas

LEASE: Higer #1  
SW/4 SW/4 NW/4  
Sec. 20, T8S, R23W  
Graham County, Kansas

COMMENCED: 12-14-56

COMPLETED: 12-23-56

FORMATION	DEPTH
Sand	36
Shale	385
Blue, Gray & Green Shale	1280
Shale, Red	1455
Dakota	1700
Red Bed	1904
Anhydrite	1938
Shale & Shells	2425
Shale & Lime	2625
Shale & Shells	2865
Shale & Lime	3296
Lime	3760
TOTAL DEPTH	3760

RECEIVED  
STATE CORPORATION COMMISSION

NOV 12 1964

CONSERVATION DIVISION  
Wichita, Kansas

11/12/64

I hereby certify that the above is true and correct to the best of my knowledge.

Mast Drilling, Inc.

*James J. Thoman*

JAMES J. THOMAN, Secty-Treas.

STATE OF KANSAS )  
                          )ss  
COUNTY OF RUSSELL)

Subscribed and sworn to before me this 3rd day of January, 1957.

*Betty Jean Suljardt*  
Notary Public

My Commission expires 8-9-58