


15-065-00359-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 22 Twp. 8 Rge. 23 (E) (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines S 1/4 S 1/4 NW
Lease Owner Glenn R. Nye et al
Lease Name Schmidt Well No. 1
Office Address Drawer 30, Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed April 15 1952
Application for plugging filed April 15 1952
Application for plugging approved April 15 1952
Plugging commenced April 15 1952
Plugging completed April 15 1952
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3991' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	119'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

First plug set at 150' with 1/2 sack hulls and 15 sacks of cement, hole filled with mud to 40'. Second plug set at 40' with 1/2 sack of hulls and 10 sacks of cement, cemented to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1952
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn R. Nye Drilling Company 428-52
Address Drawer 30, Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Glenn R. Nye
Box 30 Hays, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of April 1952
John L. Spiess
Notary Public.

My commission expires May 9, 1953

23-8800 6-51-20M
PLUGGING
FILE INC 2278 R 23 W
BOOK PAGE 9 LINE 27

Company: Glenn R. Nye et al
Contractor: Glenn R. Nye Drilling Company
Commenced: April 3, 1952
Completed: April 15, 1952

Farm: Schmidt No. 1
Location: SW SW NW Sec. 22-8-23
Graham County, Kansas
Casing Record: 8 5/8" set at 149'
Elevation: 2154' D F
Dry and Abandoned

(Figures below indicate bottoms)

sand & gravel	90		
shale	149		
shale & sand	590		
shale	940		
sand & shale	1090		
sand & shale	1180		
sand	1240		
shale & red bed	1320		
red bed	1360		
red bed & shale	1425		
red bed & shale	1450		
red bed & sand	1575		
red bed & shale	1850		
anhydrite	1880		
anhydrite	1885		
shale & shells	2050		
shale & shells	2145		
shale	2177		
shale	2380		
shale & shells	2475		
shale	2540		
shale & lime streaks	2557		
shale & lime streaks	2565		
lime & shale	2595		
lime & shale	2675		
lime & shale	2760		
lime & shale	2847		
lime & shale	2880		
lime & shale	2970		
lime & shale	3110		
shale & lime	3200		
shale & lime	3282		
lime & shale	3372	Heebner	3451
lime & shale	3455	Top K.C.	3491
lime & shale	3512		
lime & shale	3520		
cherty lime	3548		
lime	3575		
lime	3620		
lime	3667		
lime	3700		
lime	3702		
lime	3752		
lime	3795		
lime & shale	3835		
lime	3857		
shale & lime	3895		
lime	3935		
cherty lime	3945		
cherty conglomerate	3985		
cherty lime	3991	T D	

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

REC
STATE CORP
PLUGGING
FILE NO. 22-8-23
BOOK PAGE 7 LINE 27

GLENN R. NYE DRILLING COMPANY

STATE OF KANSAS)
) SS
ELLIS COUNTY)

By Glenn R. Nye

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 26th day of April, 1952.

My Commission Expires May 9, 1953

John L. Spiess
Notary Public