

15-005-20438-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Graham County, Sec. 22 Twp. 8S Rge. 23 ~~XXX~~ W (W)

Location as "NE/CNWxSWx" or footage from lines SE NW NE

Lease Owner Real Petroleum Company

Lease Name Virgil Kemp Well No. 1-V

Office Address 217 North Water, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 13, 1971

Application for plugging filed May 13, 1971

Application for plugging approved May 13, 1971


Plugging commenced May 14, 1971

Plugging completed May 14, 1971

Reason for abandonment of well or producing formation No Productible Zone

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3680 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	251	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Gunned up pits forming heavy mud. Filled hole with heavy mud. Spotted 100 sacks cement at 1080 feet. Filled hole with heavy mud. Spotted 25 sacks cement at 275 feet. Filled hole with heavy mud. Pushed wooden plug and 1/2 sack hulls to 40 feet, capped with 10 sacks cement to base of well cellar. Job complete at 1:30 AM May 14, 1971.

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Carvey Drilling Company S-19-71
Address Box 1164, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
John Chlumsky (employee of owner) _____ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John Chlumsky
Box 1164, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 19 71

My commission expires July 8, 1974

[Signature]
Notary Public.

WELL LOG

15-065-20438-00-00

COMPANY Real Petroleum Company
FARM ^{V. Kemp} V. Kemp NO. 1-V

SEC. 22 T. 8S R. 23W


LOC. SE NW NE

TOTAL DEPTH 3680'

COUNTY Graham, Kansas

COMM. 5-7-71 COMP. 5-14-71

CONTRACTOR Garvey Drilling Company



CASING
8 5/8" @ 251' w/175sx

ELEVATION

PRODUCTION D & A

FIGURE PREPARED ACCORDING TO INFORMATION

- 251' Shale & Sand
- 588' Shale
- 1375' Shale & Sand Streaks
- 1816' Shale & Sand
- 1850' Anhydrite
- 2220' Shale
- 3040' Shale w/lime
- 3140' Lime & Shale
- 3510' Lime
- 3680' Lime
- 3680' RTD

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1971
CONSERVATION DIVISION
Wichita, Kansas

8-19-71

State of Kansas }
County of Barton } ss

I, Charlene Marker of Garvey Drilling Company
upon oath state the above and foregoing is a true and correct copy of the log of the V. Kemp No. 1-V well.

Subscribed and sworn to before me this 19th day of May 19 71

My Commission Expires: July 8, 1974

Charlene Marker
Gene A. Morris
NOTARY PUBLIC