

15-065-20070-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 23 Twp. 8 Rge. 23 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE-SE-NE
Lease Owner John Jennings
Lease Name McFadden Estate Well No. 1
Office Address 311 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-1-67
Application for plugging filed 8-1 19 67
Application for plugging approved 8-1 19 67
Plugging commenced 8-1 19 67
Plugging completed 8-1 19 67
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	168'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cemented through Drill Pipe. Cemented from 1525' back to 1200' where 1st. plug was set using 100 sacks cement. Cemented from 180' back to 120' where 2nd. plug was set using 40 sack cement. Plugged at 40' where 3rd. plug was set using 10 sacks cement.

RECEIVED
AUG 8 1967
CONSERVATION DIV
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of August, 1967

My commission expires September 19, 1970

Joseph A. Glass
Notary Public.

15-065-20070-0020

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company John P. Jennings
311 Union Center
Wichita, Kansas 67202
Farm McFadden Estate No. 1

Sec. 23 Twp. 8 Rng. 23

Location NE-SE-NE

Total Depth 3615'

County Graham

Comm. 7-26-67 Comp. 8-1-67

Elevation: 2133 K.B.
2130 D.F.

Contractor L. J. Dreiling & Sons, Inc.
Victoria, Kansas 67671

2128' G.R.

Casing Record

Cement Record

Production: D & A

168' 8 5/8"

150 sacks cement

Figures Indicate Bottom of Formations

0'	40'	Sand
40'	60'	Sand & Shale
60'	161'	Shale
161'	645'	Shale
645'	1205'	Shale & Sand Streaks
1205'	1300'	Shale & Redbed
1300'	1515'	Sand
1515'	1750'	Shale & Redbed
1750'	1785'	Anhy.
1785'	1905'	Shale & Shells
1905'	2050'	Shale & Shells
2050'	2150'	Shale w/Lime Streaks
2150'	2440'	Shale & Lime
2440'	2740'	Shale & Lime
2740'	3000'	Shale & Lime
3000'	3310'	Shale & Lime
3310'	3402'	Lime & Shale
3402'	3443'	Lime
3443'	3472'	Lime
3472'	3490'	Lime
3490'	3551'	Lime
3551'	3585'	Lime
3585'	3615'	Lime
3615'	T.D.	Lime

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your McFadden Estate #1.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 7th day of August 1967

Joseph A. Hess

JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970