


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County. Sec. 23 Twp. 8S Rge. (E)23 (W)  
Location as "NE/CNW\*SW\*" or footage from lines SE NW NW  
Lease Owner Tilco, et al  
Lease Name Hull Well No. 1  
Office Address 200 Sutton Place, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-9 19 69  
Application for plugging filed 5-9 19 69  
Application for plugging approved 5-9 19 69  
Plugging commenced 5-9 19 69  
Plugging completed 5-9 19 69  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3660 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	219'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug @ 900' w/100 sacks cement  
Plug @ 240' w/20 sacks cement  
Plug @ 40' w/10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 19 1969  
CONSERVATION DIVISION  
Wichita, Kansas

5/19/69

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

SUBSCRIBED AND SWORN TO before me this 15th day of May 1969

My commission expires April 1, 1971

(Address) \_\_\_\_\_  
Ulanda Nichols  
Notary Public.

DRILLER'S LOG

COMPANY	Tilco, et al
CONTRACTOR	LEBEN DRILLING, INC.
FARM	HULL #1
LOCATION	SE NW NW SECTION 23-8S-23W GRAHAM COUNTY, KANSAS
COMMENCED	5-2-69
COMPLETED	5-9-69

-----

0	30	Clay
30	140	Sand
140	160	Sand, Shale
160	245	Shale
245	1550	Shale, Sand
1550	1797	Shale
1797	1830	Anhydrite
1830	2287	Shale
2287	3352	Shale, Lime
3352	3660	Lime
	<u>3660</u>	<u>RTD - D. &amp; A.</u>

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 19 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
5/19/69

-----

8 5/8" 20# new surface casing set @ 219' cemented with 160 sacks Common cement, 2% cc

-----

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Hull #1 Well, located SE NW NW of Section 23, Township 8 South, Range 23 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 15th day of May, 1969.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:  
April 1, 1971