

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-065-22069 ~~05-00~~

LEASE NAME Wyatt

WELL NUMBER 1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 23 TWP. 8S RGE. 23W ~~(X)~~ or (W)

COUNTY Graham

Date Well Completed \_\_\_\_\_

Plugging Commenced 1/22/98

Plugging Completed 1/23/98

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Jack Bowles

ADDRESS P O Box 3285, Edmond, OK 73083-3285

PHONE# (405) 348-4074 OPERATORS LICENSE NO. 7567

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/22/98 (date)

by Karl Goodrow & Rich Williams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation L K C Depth to Top 3497 Bottom 3628 T.D. 3870

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
L K C	oil & water	3497	3628	8 5/8"	274	none
				5.5"	3864	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Spotted 7 bbl gel plug followed with 25 sacks cement, all with 350# hulls from 3021 to 2600. Then pumped cement from 2100 to surface (200 sacks) with first 25 sacks containing hulls. Then filled top of 5.5" with 15 sacks pressured to 800 PSI. Held 200 PSI for 30 minutes before bleeding off & cutting of casing below braden head. 4' below ground

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_


Address P o Box 628, Great Bend, KS 67530 316-793-5861

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jack Bowles

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, Agent for Jack Bowles (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.



(Signature) Mike J. Fritzler

(Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 9th day of February, 1998

Debra Kerr  
 Debra Kerr Notary Public

My Commission Expires: 4/20/2001

USE ONLY ONE SIDE OF EACH FORM

*2/10/98*