

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,203-00-00

LEASE NAME Lynd

WELL NUMBER #1

SPOT LOCATION SE SE NW

SEC. 23 TWP. 8S RGE. 23W (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 5-5-86

Plugging Completed 5-7-86

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Jack Bowles

ADDRESS P.O. Box 3285 Edmund, Okla., 73080

PHONE # (405) 348-4074 OPERATORS LICENSE NO. 7567

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3839'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	267'	none
				5-1/2"	3837'	3030'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3422' and 5 sacks cement. Shot pipe @3030', pulled a total of 78 joints of 5-1/2" casing (3030'). Plugged surface with 7 sacks hulls with 250 sacks econolite.

Plugging Complete

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 86

My Commission expires:



Irene Hoover
Notary Public

STATE CORPORATION COMMISSION
MAY 14 1986
CONSERVATION DIVISION
Wichita, Kansas

LYND #1

Jack Bowles

- 23 - 8 - 23 W

15-065-22203-00-00

Sand & Clay	0	to	263	
Sand Blue Shale	263	to	946	
Sand & Shale	946	to	1774	
Anhydrite	1774	to	1808	
Shale	1808	to	2435	
Lime & Shale	2435	to	3395	
Lime	3395	to	3445	
Lime & Shale	3445	to	3485	
Lime	3485	to	3502	
Lime & Shale	3502	to	3568	
Lime	3568	to	3605	
Lime & Shale	3605	to	3695	
Lime & Chert	3695	to	3803	
Lime & Shale	3803	to	3840	R.T.D.

5/2/86
RECEIVED
STATE CORPORATION COMMISSION
MAY 02 1986
CONSERVATION DIVISION
Wichita, Kansas