


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

13-065-00011-00-00  
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County, Sec. 24 Twp. 8S Rge. 23W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW NW SE  
Lease Owner Imperial Oil of Kansas, Inc.  
Lease Name Law "B" Well No. 1  
Office Address 780 Fourth National Bldg. Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed March 19 1958  
Application for plugging filed April 8 1960  
Application for plugging approved April 14 1960  
Plugging commenced April 11 1960  
Plugging completed April 11 1960  
Reason for abandonment of well or producing formation Commercial quantities of oil depleted.  
If a producing well is abandoned, date of last production April 11 1960  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3660 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Unloaded tools, raised mast, checked hole, sanded back to 3595' mixed and run 5 sacks cement, cleaned ~~nk~~ out cellar, took tension on pipe, pulled cellar slips.  
Loaded hole with water, checked hole, shot casing at 3030', worked free and pulled 72 jts.  
Pulled 23 jts. pipe for total of 95 jts., mudded hole to 220' set 10' rock bridge, mixed and run 25 sacks cement with dump bailer, mud to 40', set 10' rock bridge with 10 sacks cement to base of cellar, well complete.

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Company S-3-60  
Address P. O. Box 364, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
K. J. Boone (employee of ~~owner~~ operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: [Signature] Pet. Engr.  
780 Fourth National Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 19 60

My commission expires July 7, 1962 [Signature] Notary Public.

15-065-00611-00-00

*R*  
DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
780 Fourth National Bldg.  
Wichita 2, Kansas

Law "B" No. 1  
NW NW SE Sec. 24-8S-23W  
Graham County, Kansas

Total Depth 3660'

Elevation: 2179' RB  
Production: 132 BOPD, No Wtr.

Commenced: 3-9-58 Completed: 3-19-58

Contractor: Imperial Oil of Kansas, Inc.  
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 220' with 150 sacks cement.

Figures indicate bottom of formations:

|                            |       |                    |             |               |
|----------------------------|-------|--------------------|-------------|---------------|
| Shale, Surface Clay & Sand | 218'  |                    |             |               |
| Shale                      | 420'  | Anhydrite          | <u>TOPS</u> | 1762' (417)   |
| Shale & Sand               | 1100' | Heebner            |             | 3394' (-1215) |
| Shale, Shells & Sand       | 1762' | Toronto            |             | 3416' (-1237) |
| Anhydrite                  | 1802' | Lansing            |             | 3430' (-1251) |
| Shale & Shells             | 2445' | Rotary Total Depth |             | 3660' (-1481) |
| Shale & Lime               | 3400' |                    |             |               |
| Lime                       | 3660' |                    |             |               |
| Total Depth                | 3660' |                    |             |               |

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: *Ray E. Brown*  
Vice-President

Subscribed and sworn to before me this 27th day of March, 1958.

My Commission Expires:  
December 19, 1960

*Luette M. Duncan*  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

MAY 3 1960

CONSERVATION DIVISION  
Wichita, Kansas

5-3-60