


15-005-00710-00-00



STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Graham County, Sec. 24 Twp. 8 Rge. 23W(E) (W)  
Location as "NE/CNW/SW" or footage from lines NE NE SE  
Lease Owner Murfin Drilling Co.  
Lease Name Lottie Law Well No. 1  
Office Address 507 Union Nat. Bank Bldg. - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 5-13 19 55  
Application for plugging filed 5-13 19 55  
Application for plugging approved 5-17 19 55  
Plugging commenced 5-13 19 55  
Plugging completed 5-13 19 55  
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3930 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	181'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud laden fluid.  
Set 1st plug at 175'  
Displaced with 1/2 sack hulls, 15 sacks cement.  
Filled hole to 40'.  
Set 2nd plug, displaced with 1/2 sack hulls, 10 sacks cement.

Name of Plugging Contractor Murfin Drilling Co. (If additional description is necessary, use BACK of this sheet)  
Address Union Nat. Bank Bldg - Wichita, Kansas 6-10-55

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. R. Murfin (employer/owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) WR Murfin

SUBSCRIBED AND SWORN TO before me this 17th day of May, 19 55.

My commission expires 6-4-55  
Abby Heimerman Notary Public.

PLUGGING  
FILE SEC 24 T 8 R 23W  
BOOK PAGE 119 LINE 12

WELL LOG


15-065-00710-00-00

COMPANY Murfin Drilling Company  
FARM Lottie Law NO. 1

SEC. 24 T. 8 R. 23W  
LOC. NE NE SE

TOTAL DEPTH 3930  
COMM. 5-3-55 COMP. 5-13-55  
SHOT OR TREATED  
CONTRACTOR Murfin Drlg. Co.  
ISSUED

COUNTY Graham  
KANSAS



CASING

20 10  
15 8 181' w/150 sx. cement  
12 6  
13 5

ELEVATION 2182 DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

25 Sand  
130 Sandy Shale  
181 Shale - Shells  
480 Shell - Sandy Shale  
895 Shale & Shells  
975 Sand  
1225 Sandy Shale  
1350 Red Bed - Shale  
1565 Sand  
1804 Shale - Shells  
1840 Anhydrite  
2150 Red Bed - Shale - Shells  
2375 Shale - Lime - Shells  
3830 Shale - Lime  
3882 Lime Shale - Chert  
3930 Lime (Arb)  
3930 RTD

Tops:

Anhydrite 1804  
Topeka 3186  
Heebner 3404  
Lansing 3444  
Marmaton 3689  
Conglomerate 3848  
Arbuckle 3880  
RTD 3930

DST #1 3630-55. Open 1/2 hr.  
Weak blow for 6 min.  
Rec. 5' mud. BHP 440#.

6-10-55

State of Kansas }  
County of Sedgwick } ss:

I, W. R. Murfin of the Murfin Drilling Company  
upon oath state that the above and foregoing is a true and correct copy of the log of the Lottie Law #1 well.

W R Murfin

Subscribed and sworn to before me this 17th day of May 19 55.

My Commission Expires: 6-4-55

PLUGGING  
FILE SEC 24 T 8 R 23W  
BOOK PAGE 119 LINE 12

Abby Heimerman  
NOTARY PUBLIC