

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: CORAL PRODUCTION CORP.
Address: 1600 STOUT ST., SUITE 1500
Phone: (303) 623-3573 Operator License #: 32639
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: 1/17/08 (Date)
by: STEVE DURRANT (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
PAWNEE Depth to Top: 4262' Bottom: 4266' T.D. 4295'
LANSING 'K' Depth to Top: 4086' Bottom: 4092' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 101-22050-00-00
Lease Name: JOE BOB JAMES Trust
Well Number: 8-1 *KCC per Reason CPAL*
Spot Location (QQQQ): _____ - NE - SE - SE
900 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 8 Twp. 16 S. R. 28 East West
County: LANE
Date Well Completed: 11/15/07
Plugging Commenced: 1/17/08
Plugging Completed: 1/21/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
4262-66'	OIL	255.24"	SURF	8 5/8"	10/10/08	N/A
4086-92'	OIL	4313'	SURF	5 1/2"	10/19/07	2450'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SAND OVER PERFS TD TO 4020'; CUT CASING @ 2450'; 50 SKS @ 2120'; 80 SKS @ 1320'; 50 SKS @ 780'; 50 SKS @ 280';
CIRC W/ 20 SKS @ 40'; CUT CSG 4' BELOW GRADE & WELD CAP

Name of Plugging Contractor: QUALITY WELL SERVICE License #: 31925

Address: 190 US HIGHWAY 56; ELLINWOOD, KS 67526

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: CORAL PRODUCTION CORP.

FEB 13 2008

State of COLORADO County, DENVER, ss.

CONSERVATION DIVISION
WICHITA, KS

JAMES R. WEBER

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) James R. Weber

(Address) 1600 STOUT ST., SUITE 1500; DENVER, CO 80202

SUBSCRIBED and SWORN TO before me this 11th day of February, 2008

Stacy R. Springton My Commission Expires: 2/1/2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



[Handwritten signature]