

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET, SUITE 1130 WICHITA, KS 67202
Phone: (316) 265-5241 Operator License #: 5042
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: 1.9.2008 (Date)
by: BRUCE BAYSE (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LANSING Depth to Top: 3201 Bottom: _____ T.D. _____
ARBUCKLE Depth to Top: 3450 Bottom: _____ T.D. 3525
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-04964-00-00
Lease Name: KOMAREK
Well Number: 1
Spot Location (QQQQ): SE - NE - NW - _____
990 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 29 Twp. 20 S. R. 12 East West
County: BARTON
Date Well Completed: 4.16.1961
Plugging Commenced: 1.9.2008
Plugging Completed: 1.10.2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		SURFACE	249	8 5/8		
		SURFACE	3525	4 1/2		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perfed at 300', 650', 1450', all with 2 shots 1.9.2008 - set plug at 3128', pumped 100sx, pulled to 1564' and pumped 60sx, pulled to 771' and pumped 110sx, could not circulate to surface. 1.10.2008 - went back in hole to 671' and pumped 200sx, circulatd to suface came out of hole, topped off with 75sx, rigged down.

Name of Plugging Contractor: EDMISTON OIL COMPANY, INC. License #: 5042
Address: 125 N MARKET, SUITE 1130, WICHITA, KS 67202

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: EDMISTON OIL COMPANY, INC.

FEB 13 2008

State of KANSAS County, SEDGWICK, ss.

CONSERVATION DIVISION
WICHITA, KS

JON M. CALLEN

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

TRUDY BOYER
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 2/19/09

(Signature) [Signature]
(Address) 125 N MARKET ST, SUITE 1130, WICHITA, KS, 67202

SUBSCRIBED and SWORN TO before me this 8 day of FEBRUARY, 20 08
Trudy Boyer My Commission Expires: 2/19/09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]

COMPANY:

E. K. Edmiston
802 Union National Bldg.
Wichita, Kansas

Rotary Drilling Commenced:

April 6, 1961

Rotary Drilling Completed:

April 16, 1961

Well Name:

Komarek No. 1
SE NE NW 29-20-12
Barton County, Kansas

Contractor:

E. K. Edmiston Drilling Co., Inc.
802 Union National Bldg.
Wichita, Kansas

Casing Record:

249' 8 5/8 w/ 250 sacks
3525' 4 1/2" w/25 sacks

LOG

Measurements from top of Rotary Bushing

Sand	0 - 140
Shale	249
Shale & shells	653
Anhydrite	676
Shale and red bed	1160
Shale and shells	1405
Lime and shale	1700
Lime	1980
Shale & lime	2150
Shale	2700
Lime & shale	2985
Lime	3003
Lime & shale	3204
Lime	3525


RECEIVED
KANSAS CORPORATION COMMISSION

FEB 13 2008

CONSERVATION DIVISION
WICHITA, KS

The undersigned, E. K. Edmiston, President of the E. K. Edmiston Drilling Co., Inc. hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

E.K. Edmiston Drilling Co., Inc.



By, E. K. Edmiston, President

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

BE IT REMEMBERED that, on this 26th day of April, 1961, before me, the undersigned, a Notary Public duly commissioned in and for the State and County aforesaid came E. K. Edmiston, known to me to be the same person who executed the foregoing instrument as President and in behalf of the E. K. Edmiston Drilling Co., Inc. and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.



Frances Marler Notary Public

My commission expires: June 25, 1964

