

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET, SUITE 1130 WICHITA, KS 67202
Phone: (316) 265-5241 Operator License #: 5042
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12-26-2008 (Date)
by: BRUCE BAYSE (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
ARBUCKLE Depth to Top: 3468 Bottom: _____ T.D. 3525

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

19127-00-00

API Number: 15 - 009-12348
Lease Name: DEWERFF B
Well Number: 3
Spot Location (QQQQ): NW - NE - SE - NW
1485 Feet from North / South Section Line
2145 Feet from East / West Section Line
Sec. 32 Twp. 20 S. R. 12 East West
County: BARTON
Date Well Completed: 1-13-1962
Plugging Commenced: 12-26-2007
Plugging Completed: 12-31-2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		SURFACE	251	8 5/8		
		SURFACE	3519	4 1/2		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perfed at 300', 640', 1500', all with 2 shots. Pumped 50sx at 3377', 95sx at 2879', 50sx at 1547', 55sx at 803', pumped cement at 400', would not circulate, used 100sx. 12-27-2007 go back in, pump 225sx at 830', circulate to surface. 12-31-2007 40sx at 400', pumped 10 more sx, pressure up to 500#, shut it.

Name of Plugging Contractor: EDMISTON OIL COMPANY, INC. License #: 5042
Address: 125 N MARKET, SUITE 1130, WICHITA, KS 67202

Name of Party Responsible for Plugging Fees: EDMISTON OIL COMPANY, INC.

State of KANSAS County, SEDGWICK, ss.

JON M. CALLEN

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N MARKET ST, SUITE 1130, WICHITA, KS, 67202

TRUDY BOYER
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 2/19/09

Subscribed and SWORN TO before me this 8 day of FEBRUARY, 20 08

[Signature] My Commission Expires: 2/19/09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 13 2008

CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]

DRILLER'S LOG

COMPANY: E. K. EDMISTON
 501 FIRST NATIONAL BANK BUILDING
 WICHITA 2, KANSAS

ROTARY DRILLING COMMENCED: 1-5-62

ROTARY DRILLING COMPLETED: 1-13-62

WELL NAME: DE WERFF B #3
 NE SE NW SEC. 32-20S-12W
 BARTON COUNTY, KANSAS

CONTRACTOR: E. K. EDMISTON DRILLING CO., INC.
 501 FIRST NATIONAL BANK BUILDING
 WICHITA 2, KANSAS

CASING RECORD: 8 5/8" @ 251' w/ 250 sacks

Measurements from top of Rotary Bushing:

0 - 200	Sand'
200 - 251	Sand & Shale
251 - 350	Shale
350 - 653	Red Bed & Shale
653 - 680	Anhydrite
680 - 1490	Shale
1490 - 1710	Shale & Lime
1710 - 2071	Lime
2071 - 2575	Shale
2575 - 2892	Shale & Lime
2892 - 3228	Lime & Shale
3228 - 3525	Lime
<u>3525</u>	<u>Rotary Total Depth</u>

The undersigned, E. K. Edmiston, President of the E. K. Edmiston Drilling Company, Inc., hereby certified, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the daily drilling reports.


E. K. Edmiston Drilling Co., Inc.

By *E. K. Edmiston*
 E. K. Edmiston, President

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

BE IT REMEMBERED that, on this 16th day of January, 1962, before me, the undersigned, a Notary Public duly commissioned in and for the State and County aforesaid, came E. K. Edmiston, known to me to be the same person who executed the foregoing instrument as President and in behalf of the E. K. Edmiston Drilling Company, Inc. and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.



Juanita M. Green
 Juanita M. Green Notary Public

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 13 2008

CONSERVATION DIVISION
WICHITA, KS

PT