

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: TNT ENGINEERING INC
 Address: 3711 MAPLEWOOD AVE SUITE 201
 Phone: (940) 691-9157 Operator License #: 33699
 Type of Well: OIL & GAS OPERATIONS Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 12/18/07 (Date)
 by: RICH WILLIAMS (VERBALLY) (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
ARBUCKLE Depth to Top: 3331 Bottom: 3414 T.D. 3429'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-02224-00-00
 Lease Name: KOLLMAN N
 Well Number: 6
 Spot Location (QQQQ): C - E/2 - SE - NE
1980 Feet from North / South Section Line
330' Feet from East / West Section Line
 Sec. 18 Twp. 11S S. R. 17 East West
 County: ELLIS
 Date Well Completed: 3/19/41
 Plugging Commenced: 12/19/07
 Plugging Completed: 12/19/07

*KCC PPT
received*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
ARBUCKLE 3331-3414	OIL/WATER	0'	35'	15.5"	35'	0'
		0'	1105'	10.75"	1105'	0'
		0'	3332'	7"	3332'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

PUMPED 120 SKS 60/40 POZ W/4% GEL DOWN TUBING @ 970'. CHECKED FOR VACUUM, THERE WAS NONE. PUMPED AN ADDITIONAL 60 SKS CEMENT DOWN TUBING, HAD CEMENT RETURNS AT SURFACE. PULLED TUBING, FILLED CASING WITH 30 SKS CEMENT.

Name of Plugging Contractor: ALLIED CEMENTING CO., LLC License #: N/A
 Address: 24 S. LINCOLN STREET, RUSSELL, KS 67665-2906
 Name of Party Responsible for Plugging Fees: TNT ENGINEERING INC.
 State of TEXAS County, WICHITA, ss
HAL GILL, ENGINEER

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 13 2008
CONSERVATION DIVISION
WICHITA, KS

_____, (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

Hal Gill

(Address) 3711 MAPLEWOOD AVE SUITE 201, WICHITA FALLS TX 76308

SUBSCRIBED and SWORN TO before me this 6 day of FEBRUARY 20 08

Susan L Van Huss
Notary Public

My Commission Expires. May 26, 2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PT



ALLIED

CEMENTING CO., LLC
Cementing & Acidizing Services

24 S. Lincoln Street
P.O. Box 31
Russell, KS 67665-2906
Voice: (785) 483-3887
Fax: (785) 483-5566

KCC

INVOICE

Invoice Number: 111746
Invoice Date: Dec 21, 2007
Page: 1

Bill To:
TNT Engineering, Inc.
3711 Maplewood
Suite #201
Wichita Falls, TX 76308

Federal Tax I.D.#: 20-5975804

Customer ID	Well Name/# or Customer P.O.	Payment Terms	
TNT	Kollman #6	Net 30 Days	
Sales Rep ID	Camp Location	Service Date	Due Date
	Great Bend	Dec 21, 2007	1/20/08

Quantity	Item	Description	Unit Price	Amount
126.00	MAT	Common Class A	11.10	1,398.60
84.00	MAT	Pozmix	6.20	520.80
7.00	MAT	Gel	16.65	116.55
470.00	SER	Handling	1.90	893.00
41.00	SER	Mileage 470 sx @.09 per sk per mi	42.30	1,734.30
1.00	SER	Plug Through Tubing	720.00	720.00
41.00	SER	Mileage Pump Truck	6.00	246.00

Voucher 116837⁹ Inv 111746
 Vendor 1929 Date 12/21
 Amt 5364.68 Disc _____
 Due 1/15 Month _____
 G. L. 57620 Sub DX 321 Lse 107963

[Handwritten Signature]

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 13 2008
CONSERVATION DIVISION
WICHITA, KS

ALL PRICES ARE NET, PAYABLE
30 DAYS FOLLOWING DATE OF
INVOICE. 1 1/2% CHARGED
THEREAFTER. IF ACCOUNT IS
CURRENT, TAKE DISCOUNT OF

\$ 562.92

ONLY IF PAID ON OR BEFORE

Jan 20, 2008

Subtotal	5,629.25
Sales Tax	298.35
Total Invoice Amount	5,927.60
Payment/Credit Applied	
TOTAL	5,927.60

[Handwritten Signature]

ALLIED CEMENTING CO., INC.

26411

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Great Bend

DATE <i>12-19-07</i>	SEC. <i>18</i>	TWP. <i>11</i>	RANGE <i>17</i>	CALLED OUT <i>6:30 AM</i>	ON LOCATION <i>9:00 AM</i>	JOB START <i>12:00 noon</i>	JOB FINISH <i>1:00 PM</i>
LEASE <i>Holloman</i>	WELL # <i>6</i>	LOCATION <i>Hays 14 north to River Rd.</i>			COUNTY <i>Ellis</i>	STATE <i>Kansas</i>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)			<i>2 1/2 east south into.</i>				

CONTRACTOR *Fisher Well Service*
 TYPE OF JOB *Plug thru tubing*
 HOLE SIZE _____ T.D. _____
 CASING SIZE *7"* DEPTH _____
 TUBING SIZE *2 1/2* DEPTH *980'*
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER *TNT*

CEMENT
 AMOUNT ORDERED *450 ex 60/40 4% Gel*
500# full on side
used 210 ex Cement

COMMON	<i>126 gal.</i>	@	<i>11.10</i>	<i>1398.60</i>
POZMIX	<i>84 gal.</i>	@	<i>6.20</i>	<i>520.80</i>
GEL	<i>7 gal</i>	@	<i>16.65</i>	<i>116.55</i>
CHLORIDE		@		
ASC		@		
<i>tools</i>	<i>See #</i>	@	<i>DIN Not USE</i>	
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<i>470 gal</i>	@	<i>1.90</i>	<i>893.00</i>
MILEAGE	<i>470 gal</i>	@	<i>41</i>	<i>1734.30</i>
TOTAL				<i>4663.25</i>

EQUIPMENT

UB
 PUMP TRUCK CEMENTER *J.D. Drailing*
 # *120* HELPER *Rick Heine*
 BULK TRUCK
 # *357* DRIVER *Joe Dammelohm*
 BULK TRUCK
 # _____ DRIVER _____

REMARKS:

KCC Witnessed ALL:
1st 980' mixed 180 ex to surface
pull all tubing. Put 7" sledge
on casing & mixed 30 ex cement.

SERVICE

DEPTH OF JOB	<i>980'</i>		
PUMP TRUCK CHARGE			<i>720.00</i>
EXTRA FOOTAGE		@	
MILEAGE	<i>41</i>	@	<i>6.00</i> <i>246.00</i>
MANIFOLD		@	
RECEIVED		@	
KANSAS CORPORATION COMMISSION		@	

FEB 13 2008

TOTAL *966.00*

CONSERVATION DIVISION
WICHITA, KS

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

TOTAL _____

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

CHARGE TO: *TNT*
 STREET _____
 CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE *X Randy Weigel*

X Randy Weigel
 PRINTED NAME

Thank you!

PS