

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warroir inc.
Address: P.o. Box 399 Garden City Ks. 67846
Phone: (620) 272-1023 Operator License #: 4058
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5/8/08 (Date)
by: Herb (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 051-22704 06 00
Lease Name: Bowlby
Well Number: #1
Spot Location (QQQQ): C - NE - NE - NE
4950 Feet from North / South Section Line
330' Feet from East / West Section Line
Sec. 27 Twp. 11 S. R. 16 East West
County: Ellis
Date Well Completed: 9/1/82
Plugging Commenced: 5/10/07
Plugging Completed: 5/10/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	400'	85/8	400'	0
		Surface	NA	51/2	NA	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Log Tech perf 1500', 525' and 425', 4spf for 1'. Ran tubing to 2016'. Swift hooked up and pumped 100sx 60/40 pos, 10% gel with 400# hulls.
Pulled tbg to 999', Swift hooked up and pumped 120sx 60/40 pos, 10% gel with 200# hulls. Pulled tbg to 340'. Swift hooked up and pumped 55 sx 60/40 pos, 10% gel with 100# hulls. Pulled tbg to 317'. Swift hooked up and pumped 60sx 60/40 pos 10% gel with 100# hulls. Cement circulated. Pulled tbg. Pumped 50sx down annulus. Hoked up to 51/2 Topped with 50sx. Cut off 6' below surface and back fill.

Name of Plugging Contractor: Western Well Drilling LLC License #: 32382 33669
Swift Services Inc. License #: 32382 33669
Address: P.O. Box 466 Nesscity Ks. 67560

Name of Party Responsible for Plugging Fees: American Warrior Inc.
State of Kansas County, Finney, ss.

FEB 11 2008

CONSERVATION DIVISION
WICHITA, KS

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

ERICA KUHLMIEIER
Notary Public - State of Kansas
My Appt. Expires 9-12-09

(Signature) [Signature]
(Address) P.O. Box 399 Garden City Ks. 67846

SUBSCRIBED and SWORN TO before me this 6 day of February, 20 08

[Signature] My Commission Expires: 09-12-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]