

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2005
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Key Gas Company
Address: 505 S. Broadway #200 Wichita, Ks. 67202
Phone: (620) 474-0162 Operator License #: 32302
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Jerry Stapleton (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-119-20906-00-00
Lease Name: Baragree Farms
Well Number: 2-19
Spot Location (OQQQ): _____ C - SE - SE
650 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 19 Twp. 34 S. R. 27 East West
County: Meade
Date Well Completed: _____
Plugging Commenced: 1-9-08
Plugging Completed: 1-11-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	773'	None
				4-1/2"	3300'	2643'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3100' and 4 sxs. cement. Cut casing loose @2643', pulled up to 1340', pumped 15 sxs. gel & 50 sxs. cement, pulled up to 800', pumped 50 sxs. cement pulled up to 400', pumped 40 sxs. cement, pulled up to 40', topped off with 30 sxs. cement, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Key Gas Corporation
State of Kansas County: Rice ss.
Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 6th day of February, 20 08

Irene Herzberg
Notary Public

My Commission Expires: _____

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]