

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2005
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Jay C. Boyer
Address: P.O. Box 511 Hays, Kansas 67601
Phone: (785) 625-3556 Operator License #: 6139
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: B.J. Hope (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-155-20,679-00-00
Lease Name: McCullough
Well Number: 1
Spot Location (OOQQ): _____ - SE - SE - SW
328 Feet from _____ North / South Section Line *KCC*
2974 Feet from East / _____ West Section Line *PKT per CP#3*
Sec. 36 Twp. 26 S. R. 8 _____ East West
County: Reno
Date Well Completed: _____
Plugging Commenced: 1-28-08
Plugging Completed: 1-30-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	216'	None
				4-1/2"	3698'	2132'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3450' and 4 sxs. cement. Cut casing loose @2132', pulled up to 961', pumped 50# hulls and 35 sxs. cement, pulled up to 625', pumped 50# hulls and 35 sxs. cement, pulled up to 326' and topped off with 110 sxs. cement, 60/40 pos, 4% gel.
Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Jay C. Boyer
State of Kansas County, Rice ss.

RECEIVED
FEB 11 2008


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the fact that the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 6th day of February, 20 08

Irene Herzberg My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202