

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-141-20, 159-00-09

NW, Sec. 18, T 9 S, R 14 W/E
2310 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6194

Lease Name Krest Well # 1

Operator: E. S. P. Development
Name & Address Lewis Eulert, Paradise, Ks.
67658

County Osborn

Well Total Depth 4010 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 271'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 626

Address P.O. Box 506, Russell, Ks. 67665

Company to plug at: Hour: 7:30 AM Day: 13 Month: 12 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Ron Burton

(company name) Emphasis Oil Operations (phone) 913-483-3518

were: Order 180 sacks 50 permix - 4% Gel - 3% Cal. Cl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 4000' w/ 20 sh. 2nd plug C 1200' w/ 20 sh. 3rd plug C 750' w/ 80 sh. 4th plug C 300' w/ 40 sh. 5th plug - solid bridge of hulk & plug C 40' w/ 10 sh. Circulate 10 sh in rat hole.

Signed G. L. Eulert (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 AM Day: 13 Month: 12 Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 271' SP. cas. w/ 150 sacks cement - 2% Gel. - 3% Cal. Cl.
Ordered 180 sacks 50 permix - 4% Gel. - 3% Cal. Cl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 4000' w/ 20 sh. 2nd plug C 1200' w/ 20 sh. 3rd plug C 750' w/ 80 sh. 4th plug C 300' w/ 40 sh. 5th plug - solid bridge of hulk & plug C 40' w/ 10 sh. Circulated 10 sh in rat hole.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Drilled into Arbuckle

DEC 21 1982

CONSERVATION DIVISION Wichita, Kansas

1221-82

I hereby certify that the above plugging instructions were given as herein stated and that I (and / did not) observe this plugging.

INVOICED
DATE 1-13-83
IV. NO. 2153-W

Signed G. L. Eulert (TECHNICIAN)