

6 070517

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-141-20,229-00-00
C-N/2-SW-5E SEC. 9, T 9 S, R 150

TECHNICIAN'S PLUGGING REPORT

Operator License # 5068

Lease Name Bersner Well # 1

Operator: Black Petroleum Company
Name & Address: 527 Union Center Bldg
Wichita, Kans. 67208
Thomas E. Black

County Ostrowe 118.95

Well Total Depth 3660 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drllg Co. License Number _____

Address Wichita, Kansas 67202 10-31-86

Company to plug at: Hour: 4:00 PM Day: 25th Month: Oct Year: 19 86

Plugging proposal received from Ken Syle

(company name) Red Tiger Drllg Inc (phone) 316-264-9342

were: 8 5/8" - 283 FT. 5P cnc w/180^{SK} 60/40 2% Ca-Cl - By allied cnt.

Proposal - Order 190^{SK} 60/40 Formix Gel - 4% Ca-Cl, 1^{SK} cello & 8 5/8" plug.
Spot with Dull Stem, Reconditioned Hb, Heavy mud between all plugs.

No circulation problems ELV. 2027, Arch. 1254, Mud condition
Viscosity 45, Weight 9.9 Water loss 9.6, spot cnt plug @ 1270 w/25^{SK}

(@870 w/100^{SK} cello) (@300 w/40^{SK} cnt) Plugging Proposal Received by _____

(@40 w/10^{SK} cnt) 15 Rat Hole cnc (TECHNICIAN)

Plugging Operations attended by Agent?: All ~~None~~ Part _____ None X

Operations Completed: Hour: 7:30 PM Day: 25th Month: Oct Year: 19 86

ACTUAL PLUGGING REPORT

Ordered 190^{SK} 60/40 Formix Gel - 2% Ca-Cl
and 1^{SK} cello slake and 1^{SK} shells, spotted with Dull Stem,

Reconditioned Hb, Heavy mud between all plugs.
1st plug @ 1270 w/25^{SK} cnt, 2nd plug @ 870 w/100^{SK} cnt cello slake,

3rd plug @ 300 w/40^{SK} cnt, 4th plug bridge plug @ 40 w/10^{SK} cnt,
15th cnt in Rat Hole (circulate)

Remarks: Cemented by Allied cnt Inc 10-30-86

INVOICED

DATE 11-3-86

INV. NO. 15265

Signed Mason Schmidt
(TECHNICIAN)