

6010141

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-141-20,201-00-00

SW, SEC. 22, T. 9 S, R. 15 W

990 feet from N/S section line

335 feet from W/P section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name Crawford Well # 5-22

Operator: Graham Michaelis

County Osborne

Name & Address Box 247

Well Total Depth 3550 115.38 feet

211 N. Broadway

Conductor Pipe: Size _____ feet

Wichita Ks

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Revlin Drlg. License Number 5671

Address Box 293 Russell Ks.

Company to plug at: Hour: 11 AM Day: 17 Month: 5 Year: 19 84

Plugging proposal received from Paula Gibson

(company name) Revlin Drlg. (phone) 913 483-5355

were: order 185 sx. cem. 50/50 por mix 6% gel, 3% cal. cl.

1-sx hulls 1-8 5/8 plug 1-sx. Flow Seal

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 2012 Anhydrite 1245-75 Arbuckle. No

Dakota. 1500 Plugging Proposal Received by Dale F. Balthazor

512 = 810

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part (None)

Operations Completed: Hour: 4:30 PM Day: 17 Month: 5 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 1250 for 15 mi.

25 sx. @ 1250

100 sx. @ 810 with 1 sx. flow seal

40 sx. @ 300, 1 sx. hulls, pushed plug to 40'

10 sx @ 40

10 sx in Rat Hole.

Remarks: Cementing Co. - Sun

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

INVOICED

DATE 5-31-84

INV. NO. 1051

Signed Dale F. Balthazor (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION MAY 29 1984 5-29-1984 CONSERVATION DIVISION Wichita, Kansas