

1-26-88 15-163-03726-00-0

6 031033

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1-31-49

C S/2 SE SW SEC. 2, T 9 S, R 16 W/E330 feet from S section line3300 feet from E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 6033Lease Name Beardmore Well # 2Operator: Murfin Drilling Co.County Rooks 105.89Name & Address Box 130Well Total Depth 3258 feetHill City, Ks. 67642Conductor Pipe: Size        feetSurface Casing: Size 5 1/2" feet 3210'Abandoned Oil Well        Gas Well        Input Well X SWD Well        D&A       Other well as hereinafter indicated       Plugging Contractor Allied Cement Co. License Number       Address Plainville, Ks.Company to plug at: Hour: PM Day: 26 Month: Jan Year: 19 88Plugging proposal received from Terry Richardson(company name) Murfin (phone)       were: 5 1/2" at 3210' w/150 sks 48' of O.H. Casing bad w/fish at 702'.Order 300 sks Common Cement and 200 sks ATL Cement Blend . 65/35 Poz 10% Gel  
2% Dical. Allied Cement Co. Company Water Trucks. Run tubing to fish.Circulate with Common Cement. Lay down pipe. Squeeze 5 1/2" casing with  
ATL Cement Blend.Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)Plugging Operations attended by Agent?: All X Part        None       Operations Completed: Hour: 6:30PM Day: 26 Month: Jan Year: 19 88ACTUAL PLUGGING REPORT Ran tubing to 680'. Pump 100 sks Common Cement. Circulate  
on backside. Close in backside. Pump 200 sks Common Cement through tubing to  
full circ. Lay down tubing. Squeeze backside w/25 sks ATL Cement Blend to 500#. Squeeze  
5 1/2" w/25 sks. ATL Cement Blend to 600#. Close in at 300#. Plug complete.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby agree to serve this plugging.DATE 2-15-88Signed Carl Goodrow  
(TECHNICIAN)  
Carl GoodrowINV. NO. 19852

1-26

FORM CP-2/3  
Rev. 01-84 LR