

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-19025-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 2-9S-16W  
330 feet from S Section Line, 4950 feet from W Section Line  
Lease/Unit Name: BEARDMORE Well Number: 9  
County: ROOKS Total Vertical Depth: 3399 feet

Operator License No.: 101  
Op Name: KCC FEE FUND  
Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 180  
Production: Size 5.5 feet: 3395  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/01/2002 11:00 AM

Plug Co. License No.: 32579 Plug Co. Name: PFEIFER DOZER SERVICE, LLC

Proposal Rcvd. from: LEON PFEIFER Company: PFEIFER DOZER SERVICE, LLC Phone: (785) 627-5711

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Perforated salt section at 1825'. Anhy at 1300'. Dakota at 775'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/01/2002 12:15 PM

KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Perf Tech perforated salt at 1825'. Anhy at 1300'. Dakota at 775'.  
Fluid level 3195'.  
PBTB 3360'.  
Allied pumped 275 sxs 60/40 pozmix - 10% gel with 500# hulls.  
No pressure.  
Checked backside instant 400# pressure.  
May 2, 2002 - Cement down 200' and topped off with 25 sxs.

RECEIVED  
MAY 29 2002  
5-29-2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams  
(TECHNICIAN)

MAY 22 2002

2-9-16W

BROADVIEW OIL COMPANY, #9 BEARDMORE SW SW SW

Contr. BENNETT & ROBERTS ROOKS County


E 2023RB Comm. Comp. 5-29-59 IP 25 BOPD

| Tops | Depth | Datum |
|------|-------|-------|
| HEEB | 3090  | -1067 |
| TOR  | 3115  | -1092 |
| KC   | 3135  | -1112 |
| B/KC | 3395  | -1372 |
| TD   | 3399  | -1376 |

Casing  
 8" 180  
 5" 3395

PERF 3238-44: 3313-24: 3302-04  
 3276-82: ACID 3500

LATON POOL



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

10/10/2014 10:10:10 AM 10/10/2014 10:10:10 AM 10/10/2014 10:10:10 AM 10/10/2014 10:10:10 AM 10/10/2014 10:10:10 AM