

6 040329

API NUMBER 15-163-19190-00-00 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N2NW, SEC. 2, T. 9 S, R. 16 W/B

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Baxter Well # B-#2

Operator: Murfin Drilling Co.

County Rooks

Name: _____

Well Total Depth 3480 10' 50" feet

Address 250 N. Water

Conductor Pipe: Size _____ feet

S. 300

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 217' w/200 sx

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sun Conty Co. License Number _____

Address Hays, Kansas

Company to plug at: Hour: 10:15 Day: 11 Month: 12 Year: 19 84

Plugging proposal received from Jerry Richardson

(company name) Murfin (phone) _____

were: 4 1/2" @ 3399' w/150 sx, perf. @ 3104-3350

Fish in hole @ 2478'

Ordered 450 sx. 50% poz. 6% gel-3% cc box hulls & 1/4" flo-
cel. & 4 1/2" w. plugs.

*(replied to M. Schmidt)
for plug rec.*

Plugging Proposal Received by Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4:30 pm Day: 11 Month: 12 Year: 19 84

ACTUAL PLUGGING REPORT Ran tbg to 2450', pumped 75 sx emt
w/2 hulls, pulled tbg to 1250', pumped 70 sx emt w/2
hulls pulled to 500', circ emt to surf w/70 sx,
pulled tbg, squeezed to 500' w/15 add sx. Hooked-up
to 8 5/8, pumped in 220' sx emt - P.S.T. 900# MAX
Shut-in 500'

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED
If you did not observe this plugging.

DATE 6-18-85

Signed Dennis Hamel
(TECHNICIAN)

INV. NO. 8554

72-11-84