

6 040328

API NUMBER 15-163-30191-00100

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

CS252NW, SEC. 2, T. 9 S, R. 16 W/E

_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Baxter Well # A-7

Operator: Murphy Drilling Co.

County Rooks

Name & Address 250 N. Water

Well Total Depth 3368 ^{109.46} feet

S. 300

Conductor Pipe: Size _____ feet _____

Wichita, Ks 67202

Surface Casing: Size 8 5/8 feet 209' w/ 175' w/

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Emty. License Number _____

Address Hays, Kansas

Company to plug at: Hour: 6:00 P.M. Day: 20 Month: 2 Year: 19 85

Plugging proposal received from Terry Richardson

(company name) Murphy Drilling Co. (phone) _____

were: 5 1/2" csg set @ 3367' w/ 200 sx cnt, 2 3/8" tbg

w/packer @ 3306', Top of fish @ 901', well gauged

@ 780' w/ 200 sx, Holes in csg,

Ordered 300 sx 60/40 prog, 10% gel & 6 sx hulls

Plugging Proposal Received by Dennis J. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 10:00 PM Day: 20 Month: 2 Year: 19 85

ACTUAL PLUGGING REPORT

Ran tbg. to 893' pmpd in 30 sx. cnt; pulled

tbg. to 235', pmpd in 35 sx. cnt; pulled

remaining tbg. squeezed in add. 190 sx cnt. P.S.I.

to 300 #, shut-in P.S.I. (158 #). (mixed hulls w/ all cnt)

Hooked-up to 8 5/8" S.P.; pmpd in sx 140 cnt; P.S.I. 350 #

Remarks: Shut-in P.S.I. 150 #

(If additional description is necessary, use BACK of this form.)

INVOICED

(To be observed) observe this plugging.

DATE 6-18-85

Signed Dennis J. Hamel
(TECHNICIAN)

6-12-1985

INV. NO. 8545