

6 040388

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-02829-00-00 <sup>R</sup>

CNW4, SEC. 3, T. 9 S, R. 16 W

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Gamble Well # 6

Operator: Co-Co/Murphy Dily Co.

County Rooks

Name & Address 250 N. Water

Well Total Depth 3456' 112.32 feet

S. 300

Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_

Wichita, Ks 67202

Surface Casing: Size 7" feet 1288' w/ 300' w

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor Halliburton Int'l License Number \_\_\_\_\_

Address Hays, Ks

Company to plug at: Hour: \_\_\_\_\_ Day: 28 Month: 3 Year: 19 85

Plugging proposal received from Pat Canady

(company name) Murphy Dily (phone) \_\_\_\_\_

were: 4 1/2" csg. set @ 3447' w/ 50 sy cement.

junk in hole - moved in rig to wash over - (Day 23 - ran  
1/2" line pipe to 210' couldn't get any deeper - between 4 1/2" annulus)  
(Day 24 - drilled & milled to 685' - couldn't get any deeper  
(consult w/ Don Butcher) decided to plug here. Ordered 350 sy.

Plugging Proposal Received by Dennis L. Jamel <sup>Common</sup>  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 28 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT

Ran tbg to 675' - pumped 85 sy common cire to surf - pulled  
tbg - pumped add 50 sy cement cire out of braden head  
shut-in braden head, pumped in add 10 sy cement - P.S.I to 1800#  
hooked-up to braden head, pumped 50 sy cement, cire out of 4 1/2" csg.  
shut-in 4 1/2" csg & pressured up to 600# & shut-in.

Remarks: \_\_\_\_\_ (If additional description is necessary, use BACK of this form.)

INVOICED (did/did not) observe this plugging.

DATE 6-18-85

Signed Dennis L. Jamel  
(TECHNICIAN)

INV. NO. 8548