

6 041255
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-26 15-163-03590-00-00
API NUMBER 15- NA
C NW NW, SEC. 3, T 9 S, R 16 W/E^{XX}
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9854

Operator: Mar Mac Pet Co
Name & Address 2120 So. Holly S. 207
Denver, Colorado 80222

Lease Name Gamble Well # 2
County Rooks 105.95

Well Total Depth 3260 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 73 w/55 sks.

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing #9317 License Number _____

Address Russell, Ks.

Company to plug at: Hour: 9:00 AM Day: 26 Month: _____ Year: 19 90

Plugging proposal received from Don Brungardt

(company name) Marmac Pet. (phone) _____

were: 5 1/2 casing set at 3132 w/150 sks. cement: perms at 3258 to 3133; Perf anhy at

1310; Perf base dakota at 750. R.I.H. w/tubing to 2170 - ? 4 1/2 liner. 3109 - 3260.

Ordered 300 sks 65/35 poz 10% gel w/1/4 lb f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11:30AM Day: 26 Month: Oct. Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2 casing w/25 sks cement w/1/4 lb f.c. plus pumped in

add 250 sks cement w/1/4 lb f.c. and 4 sks hulls mixed in cement. Max 900 lbs. S.I. 400 lb.s

Pumped in 8 5/8 casing w/50 sks cement w/1/4 lb f.c. and 1 sk hulls mixed in cement.

Max 600 lbs. S.I. 600 lbs.

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1990
11-30-1990

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-7-90

INV. NO. 30171

JAN 10 1991

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis Hamel