

6 040386

API NUMBER 15-163-03987-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NESW SEC. 3, T. 9 S, R. 16 W/8

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Baxter 'E' Well # 6

Operator: Murphy Drilling Co.

County Rooks Co.

Name & Address 250 N. Water

Well Total Depth 3100 ^{100.75} feet

S. 300

Conductor Pipe: Size _____ feet _____

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 65' w/ 40sx

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Entg License Number _____

Address Hays, Kansas

Company to plug at: Hour: 2:00 PM Day: 17 Month: 4 Year: 19 85

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 5 1/2" csg set @ 3100' w/ 125 sx - perfs @ 2968' - 3053'
csg bad 620' - 1129'

Ordered 300 sx 6 1/4 pg 8 7/8 gel, 12 sx gel, 19 sx hulls Co. Well run tbg

Plugging Proposal Received by Dennis J. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 2:00 PM Day: 17 Month: 4 Year: 19 85

ACTUAL PLUGGING REPORT Ran tbg to 2842' & spotted 25 sx cmt w/ 1 sx hulls, pulled to 2507' & spdl 12 sx gel, pulled tbg to 1295' & spdl 50 sx cmt w/ 3 sx hulls, pulled tbg to 710' & spdl 100 sx cmt w/ 6 sx hulls, cmt circ to surf. pulled tbg & pumped add. 25 sx cmt - P.S.I 300 # hooked up to 8 5/8" & pumped in 75-100 sx cmt w/ 2 sx hulls.

Remarks: P.S.I 300 # M.A.X
(If additional description is necessary, use BACK of this form.)

NOTICED (did not) observe this plugging.

DATE 6-18-85

INV. NO. 8546

Signed Dennis J. Hamel
(TECHNICIAN)

JUN 12 1985
6-13-1985