

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19022-00-00⁰¹
Spot: SWNWNE Sec/Twnshp/Rge: 3-9S-16W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: BAXTER E Well Number: W7
County: ROOKS Total Vertical Depth: 3354 feet

Operator License No.: 9854
Op Name: MARMAC PETROLEUM COMPANY
Address: 2120 S. HOLLY STREET, STE 207
DENVER, CO 80222

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 217 w/200 sxs cmt \$109.01
Production: Size 4.5 feet: 3354 w/150 sxs cmt
Liner: Size feet:

Well Type: EOR UIC Docket No: E11333.2 Date/Time to Plug: 10/25/2001 9:00 AM
Plug Co. License No.: 6569 Plug Co. Name: SCHMITT, CARMEN, INC.
Proposal Rcvd. from: CURTIS HITSCHMAN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 600# hulls.
Perfs 3084' - 3295'.
Well was squeezed at 518' - 730' w/350 sxs; 2036' - 2060' w/100 sxs.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/25/2001 10:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied Cementing Company tied onto backside and pumped 1/2 barrel cement. S.I.P. 500#.
Tied onto casing and pumped 225 sxs 60/40 pozmix with 600# hulls.
Max. P.S.I. 725#. S.I.P. 150#.

Note: Marmac Petroleum Company abandoned this lease.
Carmen Schmitt bought this lease at a courthouse auction.
No T-1 available.

Remarks: ALLIED CEMENTING COMPANY - TICKET #10376.

Plugged through: CSG

District: 04

Signed Pat Staab

(TECHNICIAN)

RECEIVED

INVOICED

Form CP-2/3

NOV 01 2001
11-1-2001
KCC WICHITA

DATE 11-1-01
INV. NO. 2002060890

OCT 29 2001

BROADVIEW OIL CO

#7 BAXTER 'E'

3-9-16W
SW NW NE

Contr. D & D DRLG

ROOKS

County

E 1961 KB Comm. 1/22/64

Comp. 2/13/64

IP PMP 20 BOPD + 40 BOPD
(LANS 3084-3295)

SMP Tops	Depth	Datum
1258		
TOP	2828	-867
HEEB	3034	-1073
TOR	3058	-1097
LANS	3074	-1113
B. KC	3342	-1381
RTD	3355	-1394

Casing

8" 217/190 sx:


518-730

4" 3354:

NO TESTS: NO LOG:

CO 3325: 7/3292-95: 11/3269-74:
17/3240-48: 17/3218-26: 15/3173-
85: 9/3171-75: 7/3160-63: 15/3138-
44: 15/3110-16: 11/3095-3100: 9/
3084-88: A 16,000: REC LD: 0/S:
POP: ...

LATON



GEOL: JIM DANIELS:

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS