

4-020123

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API number: 15-163-23,291-0000

12-9

NE SW NW /4 SEC. 12, 09 S, 16 W
3630 feet from S section line
4290 feet from E section line

Operator license# 31514

Lease: Graham Well # 1

Operator: Thoroughbred Associates, LLC
Address: 10 Colonial Court
Wichita, Kansas 67207

County: Rooks 113.88
Well total depth 3504 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 1/2 Inch @ 217 feet

Aband. oil well _____, Gas well _____, Input well _____, SWD _____, D & A X

Plugging contractor: Shields Drilling Company, Inc. License# 05184

Address: P.O. Box 709, 326 Main, Russell KS 67665-0709

Company to plug at: Hour: _____ Day: 09 Month: December Year: 1996

Plugging proposal received from: Burt Beery

Company: Shields Drilling Company, Inc. Phone: 913 483 3141

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ <u>1330</u> feet with <u>25</u> sacks	Rat hole: <u>15</u> sacks
2nd plug @ <u>840</u> feet with <u>100</u> sacks	Mouse hole: <u>10</u> sacks
3rd plug @ <u>270</u> feet with <u>40</u> sacks	
4th plug @ <u>40</u> feet with <u>10</u> sacks	

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 3:30 PM, Day: 09, Month: December, Year: 1996

Actual plugging report: Hole reported plugged as above.

Order 225 sx 60/40 pozmix w/ 6% gel and 2.0 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cement job.

Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____

Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____

Plugged through TUBING _____, CASING X. Elevation: 2068 GL

and agent [X] observe the plugging.

[Handwritten Signature]
(agent)

INVOICED

DATE DEC 13 1996

INV. NO. 47177