

11-6-87

6 040813

API NUMBER 15-Ne3-03600-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SW, SEC. 13, T 9 S, R 16 W/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6597

Lease Name DoDr Well # 3

Operator: A. H. Kruger
Name & Address: 211 Circle Drive
Hays, Kansas 67601

County _____ Rooks 112.65
Well Total Depth 3466 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 100' cwc

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cement License Number _____

Address Hays, Kansas

Company to plug at: Hour: 9:00AM Day: 6 Month: Nov Year: 1987

Plugging proposal received from Dean Wineland

(company name) A. H. Druger (phone) _____

were: 5 1/2" set at 3466' w/100 sks cement. Perf at 3221' - 3298'. Holes in casing at 905' to 553' sq w/300 sks cmt. Hole in casing at 1495. Ordered 150 sks 65/35 Poz 10% Gel 2% Lite-w/1/4# Flocele per sk plus 8 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 AM Day: 6 Month: Nov Year: 19 87

ACTUAL PLUGGING REPORT Ran tubing to 1495' circ. cmt to surface w/75 sks cement w/8 sks Hulls.

Pulled tubing. Hooked up to 5 1/2" casing. Pumped in 30 sks cement. Circ. cement through 10 3/4" S.P., Shut in same. Pumped in add. 50 sks cement. Max Psi 300# S.I. 100#

Witnessed by Gil Balthazor

11/30/87 13730137
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-4-87

Signed Dennis L. Hamel (TECHNICIAN) Dennis Hamel

INV. NO. 19119