

4 060160

2-11

204
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-21,069 -00-00

SE NE NE, SEC. 5, T. 9 S, R 16 W/E

4290 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name Dunlap Well # 2

Operator: State of Kansas Fee Fund
Name & Address _____

County Rooks

Well Total Depth 3385 feet

Jay Baker purchased from CPI.

Conductor Pipe: Size _____ feet

filed bankruptcy before well could be plugged.

Surface Casing: Size 8 5/8 feet 171

Abandoned Oil Well XXXXXXXX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor State of Kansas KCC License Number _____

Address KCC District #4 Hays, KS

Company to plug at: Hour: 8:00AM Day: 11 Month: February Year: 19 91

Plugging proposal received from Herb Deines & Dennis Hamel

(company name) KCC district staff (phone) _____

were: Run tubing to TD and cement to surface.

Order 350 sxs. 65/35pos 8%gel and hulls.

2-21-1991
FFR 21 1991

CONSERVATION DIVISION
WICHITA, KANSAS

Plug had been pumped to 2700' and verified with cement tickets and tag on bottom with tubing. Casing shot off and pulled from 670' to surface.

Plugging Proposal Received by Herb Deines & Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXX Part _____ None _____

Operations Completed: Hour: 2:00PM Day: 11 Month: February Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" to 171', 5 1/2" at 3380'. Shot off and recovered 670' 5 1/2"

Ran tubing to 1250 and perforated anhydrite at 1270'. Ran tubing on to 2670' and tagged bottom plug. Pmp 150 sxs. cement and pulled tubing to 700'. Pmp 144 sxs. cement to circ cement to surface. Pulled tubing and tied onto casing. Pmp 50 sxs. cement.

Max 250# SIP 200#.

Remarks: B-J Services Cementing, Great Guns Perforators, Plant Water Serv. Bill's Well Serv.
(If additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

Gilbert

Signed Dennis Hamel
(TECHNICIAN)

Dennis Hamel

Herb Deines