

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

Correction (on Range)

API Well Number: 15-163-22092-00-00 01
Spot: SWSWSW Sec/Twnshp/Rge: 6-9S, 16W
220 feet from S Section Line, 4880 feet from E Section Line
Lease/Unit Name: KERN Well Number: 1
County: ROOKS Total Vertical Depth: 3460 feet

Operator License No.: 8735
Op Name: S & M OIL
Address: 2730 THUNDERBIRD DR.
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 275 /140 sxs cmt.
Production: Size 5.5 feet: 3458 /150 sxs cmt.
Liner: Size feet:

Well Type: EOR UIC Docket No: E22.292 Date/Time to Plug: 09/27/2000 8:00 AM
Plug Co. License No.: 8735 Plug Co. Name: S & M OIL
Proposal Rcvd. from: STEVE CRAWFORD Company: S & M OIL Phone: (785) 650-4003

Proposed 5 1/2" casing set at 3458' w/150 sxs cmt.
Plugging Perf at 3306' - 3358'.
Method: D.V. Anhy at 1275' w/275 sxs cmt.
TOF at 200'.
Ran W.L.M. to 1650', indicating bad pipe-casing. Very rough when operator pulled tubing and packer.
Ordered 325 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/28/2000 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

09-27-1000 - R.I.H. with tubing to 1350'. Spotted 150 sxs cement with 600# hulls. No circulation at surface. Shut down.
09-28-2000 - Ran W.L.M. to 1346' - hard cement.
R.I.H. with tubing to 1348' - stacked out tubing and pulled up to 1310'.
Spotted 3 sxs gel followed with 100 sxs cement w/200# hulls cwc.
POOH with tubing and squeezed 15 sxs cement. Max. P.S.I. 300#.
R.U. Cementers to 8 5/8" S.P. - pressured up 700#. Job complete.

RECEIVED
STATE CORPORATION COMMISSION
MAR 9 2001
3-9-2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks:

Plugged through:

District: 04

Signed 151 Dennis Hamel
(TECHNICIAN)

REPLACEMENT CARD

S & M OIL
 205 N. JEFFERSON
 PLAINVILLE, KS. 67663


#1 KERN

6-9-16W
 200'FSI &
 400'FWL, SW/4

CONTR LOBO DRILLING CO. CTY ROOKS

GEOL _____ FIELD WESTHUSIN EAST

ELV 1983 KB SPD 8/2/83 CARD ISSUED 1/12/84 IP P 4 BO & 4 BWPD
1978 GL DRLG COMP 8/9/83 LKC 3306-3363 OA
 API 15-163-22,092



LOG	Tops	Depth/Datum	
			8 5/8 " 275, 5 1/2 " 3458
			NO CORES OR DSTS
*ANH	1277+	706	MICT - CO, PF (LKC) 3350-3355 & 3357-3363, W / 2 SPF, AC
*B/ANH	1311+	672	500 GAL (15% MA), SWB LD, SO, RE-AC 1000 GAL (15% REG),
TOP	2882-	899	SWB LD, SO, PF (LKC) 3327-3330 & 3320-3324, W / 2 SPF, AC
HEEB	3098-	1115	750 GAL (15%), SWB LD, SO, PF (LKC) 3306-3310, W / 2 SPF,
LANS	3141-	1158	AC 1000 GAL (15%), SWB LD, SO, POP, P 4 BO & 4 BWPD, 9/15/
BKC	3388-	1405	83
ARB	3432-	1449	
RTD	3460-	1477	
*DRILLERS TOPS			

INFO RELEASED: 12/25/86 - ADDED LOG TOPS

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS