

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: ⁰¹ ~~15-163-22092-00-06~~
Spot: SWSWSW Sec/Twnshp/Rge: 6-9S-17W
220 feet from S Section Line, 4880 feet from E Section Line
Lease/Unit Name: KERN Well Number: 1
County: ROOKS Total Vertical Depth: 3460 feet

Operator License No.: 8735

Operator Name: S & M OIL

Address: 2730 THUNDERBIRD DR.
HAYS, KS 67601

Conductor Pipe: Size

Surface Casing: Size 8.625

Production: Size 5.5

Liner: Size

feet:

feet: 275

feet: 3458

feet:

112.45

Well Type: EOR

UIC Docket No: E22,292

Date/Time to Plug: 9/27/00 8:00:00 AM

Plug Co. License No.: 8735

Plug Co. Name: S & M OIL

Proposal Rcvd. from: STEVE CRAWFORD

Company: S & M OIL

Phone: (785) 650-4003

Proposed 5 1/2" casing set at 3458' w/150 sxs cmt.

Plugging Perf at 3306' - 3358'.

Method: D.V. Anhy at 1275' w/275 sxs cmt.

TOF at 200'.

Ran W.L.M. to 1650', indicating bad pipe-casing. Very rough when operator pulled tubing and packer.
Ordered 325 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 09/28/2000 12:00 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

09-27-1000 - R.I.H. with tubing to 1350'. Spotted 150 sxs cement with 600# hulls. No circulation at surface. Shut down.
09-28-2000 - Ran W.L.M. to 1346' - hard cement.
R.I.H. with tubing to 1348' - stacked out tubing and pulled up to 1310'.
Spotted 3 sxs gel followed with 100 sxs cement w/200# hulls cwc.
POOH with tubing and squeezed 15 sxs cement. Max. P.S.I. 300#.
R.U. Cementers to 8 5/8" S.P. - pressured up 700#. Job complete.

RECEIVED
STATE CORPORATION COMMISSION

OCT 4 2000

10-4-2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks:

Plugged through:

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

DATE 10/9/00

INV. NO. 2001060804

Form CP-2/3

OCT 02 2000