

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20928-00-00
Spot: SENWNWSW Sec/Twnshp/Rge: 7-9S-16W
4640 feet from S Section Line, 4840 feet from E Section Line
Lease/Unit Name: HUTTON B Well Number: 2
County: ROOKS Total Vertical Depth: 3425 feet

Operator License No.: 8735
Op Name: CRAWFORD, STEPHEN G. DBA S & M OI
Address: 1725 250TH AVE.
HAYS, KS 67601

Conductor Pipe: Size feet: 3 1/1.31
Surface Casing: Size 8.625 feet: 169 100 SX CMT
Production: Size 4.5 feet: 3424 130 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/06/2002 8:00 AM
Plug Co. License No.: 8735 Plug Co. Name: CRAWFORD, STEPHEN G. DBA S & M OIL
Proposal Rcvd. from: STEVE CRAWFORD Company: CRAWFORD, STEPHEN G. DBA S & M OIL Phone: (785) 650-4003

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 700# hulls.
Tubing fish at 835'.
Holes in the casing.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/06/2002 12:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing to 825' to T.O.F.
Spotted 25 sxs 60/40 pozmix - 10% gel, followed with 25 sxs cement with 150# hulls to circulate at surface.
POOH with tubing.
R.U. Cementers to 4 1/2" casing - squeezed 150 sxs cement.
Max. P.S.I. 700#. S.I.P. 500#.
8 5/8" S.P. - 25 sxs with 100# hulls.
Max. P.S.I. 400#. S.I.P. 200#.

RECEIVED
AUG 16 2002
8-16-2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

DATE 8-19-02


TEL. NO. 2003860237

Form CP-2/3

AUG 07 2002

REPLACEMENT CARD

S & M OIL
 205 N. JEFFERSON #1 KERN 6-9-16W
 PLATVILLE, KS. 67663 200'ESI &
 CONTR LOBO DRILLING CO. CTY ROOKS 400'FWL, SW/4
 GEOL _____ FIELD WESTHUSIN EAST
 ELV 1983 KB SPD 8/2/83 CARD ISSUED 1/12/84 IP P 4 BO & 4 BWPD
 1978 GL DRLG COMP 8/9/83 LKC 3306-3363 OA
 API 15-163-22,092



LOG	Tops	Depth/Datum
*ANH	1277+ 706
*B/ANH	1311+ 672
TOP	2882- 899
HEEB	3098-1115
LANS	3141-1158
BKC	3388-1405
ARB	3432-1449
RTD	3460-1477
*DRILLERS TOPS		

8 5/8 " 275, 5 1/2 " 3458
 NO CORES OR DSTS
 MICT - CO, PF (LKC) 3350-3355 & 3357-3363, W / 2 SPF, AC
 500 GAL (15% MA), SWB LD, SO, RE-AC 1000 GAL (15% REG),
 SWB LD, SO, PF (LKC) 3327-3330 & 3320-3324, W / 2 SPF, AC
 750 GAL (15%), SWB LD, SO, PF (LKC) 3306-3310, W / 2 SPF,
 AC 1000 GAL (15%), SWB LD, SO, POP, P 4 BO & 4 BWPD, 9/15/
 83

INFO RELEASED: 12/25/86 - ADDED LOG TOPS