

STATE CORPORATION COMMISSION

JUN 03 1983 6-3-1983

CONSERVATION DIVISION  
Wichita, Kansas

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- -

NE-NE-NE Sec. 10, T 9 S, R 16 W/E

feet from N/S section line

feet from W/E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5769

Lease Name Beardmore Well # 7

Operator: Harold Kruger Co.  
Name & Address Box 247  
Natoma, Kansas  
67651

County Rooks

Well Total Depth 3192 feet \$103.74

Conductor Pipe: Size - feet -

Surface Casing: Size NONE

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Emtp License Number

Address Hays, KS

Company to plug at: Hour: 12:00PM Day: 9 Month: 5 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Dean Wineland

(company name) H. Kruger Co. (phone)

were: 5 1/2" set @ 3143 w/150 sx - open hole -> Hold in csg @ 924'  
(5-5-83) Rmptd 1 1/2 bbl p.m. @ 200# -> ran line to 2986' -> rmpd 3 bbl p.m.  
@ 300# -> rmpd 150 sx emt w/4-hulls @ 1 bbl p.m. w/500#  
ran plug to 800' -> Shut-in = (5-9-83) plug back to  
543' -> Perf @ 500' -> rmpd in 2 bbl p.m. @ 300# -> rmpd 50 sx  
w/hulls - PSI. to 600# (cont. below)

Signed (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:00PM Day: 9 Month: 5 Year: 1983

ACTUAL PLUGGING REPORT

rmpd plug to 425' w/1400# PSI -> perf @ 250'  
pressure to 500# (no rate) -> Perf @ 150' circ emt  
to surface w/85 sx emt -> PSI. to 1450#  
Shut-in 900#

Remarks:

I hereby certify that the above plugging instructions were given as herein stated and that I (did) did not) observe this plugging.

Signed Dennis L. Hamel (TECHNICIAN)

INVOICED  
DATE 6-8-83  
INV. NO. 4515-W