

15-163-03735-00-01
5-16-88Not a computer
document #?

6 040894

API NUMBER 15- 09-23-40

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

CS2 NE SW, SEC. 10, T 9 S, R 16 (W) 28

1650 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name Bu11 (Buell) Well # #2 SWD

Operator: Harold Kruger Co.

County Rooks

Name &

Address Natoma, Kansas,

Well Total Depth 3430 feet

67651

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 104

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cmtg. Co. License Number _____

Address Hays, Kansas (Larry Dinkel) #418625

Company to plug at: Hour: 11:30 am Day: 16 Month: 5 Year: 19 88

Plugging proposal received from Dean Wineland

(company name) Harold Kruger Co. (phone) _____

were: 5 1/2" casing set @ 3430'. Perfs @ 3217-27', 3237-39', 3245-50'. Perf casing @ 900'
and 1250'. Run tubing to 1340' (4 1/2" liner to 400'). Packer and tubing stuck in hole
below 2000'. Ordered 50 sx common plus 150 sx 65/35 pozmix, 10% gel, w/ 1/4 flocele.

Plugging Proposal Received by

Dennis L. Hamel

(TECHNICIAN)

Dennis L. Hamel

Plugging Operations attended by Agent?: All _____ Part XX None _____

Operations Completed: Hour: 11:30 am Day: 16 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT Ran tubing to 1340', pumped in 35 sx cmt plus 110 sx econolite w/ 1/4
sack flocele, then pulled tubing. Pumped additional 10 sx cmt, pressured up to 300#-
Shut in 300#.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

(X) (if not) observe this plugging.

Signed

Dennis L. Hamel

(TECHNICIAN)

Dennis L. Hamel

FORM CP-2/3
Rev. 01-84

DATE

7-25-88

INV. NO.

21634

Ok. G. S.