

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02832-00-00  
Spot: SWSESENW , Sec/Twnshp/Rge: 11-9S-16W  
2690 feet from S Section Line, 3040 feet from E Section Line  
Lease/Unit Name: LIVINGOOD Well Number: W-10  
County: ROOKS Total Vertical Depth: 3460 feet

Operator License No.: 100  
Op Name: KANSAS CORPORATION COMMISSION  
Address: 130 S MARKET RM 2078  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 1323  
Production: Size 4.5 feet: 3459  
Liner: Size \_\_\_\_\_ feet:

Well Type: WSW UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/18/2001 11:30 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Found no 4 1/2" casing in wellbore, only 8 5/8".  
Plugging Well was converted to WSW in upper Dakota.  
Method: PBTD 553'. Fluid Level 300'.  
Ordered out 145 sxs 60/40 pozmix - 300# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/18/2001 12:30 PM

KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Rigged Allied up to 8 5/8" casing and pumped 145 sxs 60/40 pozmix - 10% gel with 300# hulls.  
Max. P.S.I. 600#. S.I.P. 400#.

2/5/01  
RECEIVED  
FEB - 2 2001

Remarks: ALLIED CEMENTING COMPANY. SPOT LOCATION READS AS FOLLOWS: 400'W. & 50'N. OF C. OF SEC. 11-09-16.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

Invitation For Bid Number 02291

Page 33

BROADVIEW OIL CO 1W-10 LIVINGOOD 11-9-16W  
 400' W & 50'  
 N OF CEN OF SEC  
 Contr. SHIELDS DR LG \_\_\_\_\_ ROOKS \_\_\_\_\_ County

E. 2074 KB Comm. 7/29/64 Comp. 9/3/64 IP. WTR INJ WELL - RATE

SATISFACTORY (LANS 3183-

LOG Tops	Depth	Datum
TOP	2936	-862
HEEB	3161	-1087
TOR	3181	-1107
LANS	3202	-1128
RTD	3460	-1386

Casing 3312)

8" 1323/650 sx:

4" 3459/125 sx:

NO TESTS:


RTD 3460: 4" 3459: 13/3183-87: 7/

3202-04: 19/3214-20: 10/3225-28:

25/3238-46: 13/3256-60: 16/3297-

3302: 16/3307-12: 2" TBG TO 3000'

LATON



GEOL: JIM DANIELS:

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS