

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03748-00-00
Spot: CW2SWNE Sec/Twnshp/Rge: 11-9S-16W
3300 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: LIVINGOOD Well Number: C-2
County: ROOKS Total Vertical Depth: 3258 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 0
Production: Size 4.5 feet: 3247
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/25/2001 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 1200# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/25/2001 5:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Lost circulation while washing thru bridges at 525' to 589'.
Found casing collapsed at 589'.
Located rotary rig 10 miles away just finished D/A on January 25, 2001.
Hauled 160 BBL's. drilling mud from reserve pit and pumped down 4 1/2" casing. on last 15 bbl's caught 150# on casing.
Allied followed drilling mud with 350 sxs 60/40 pozmix - 10% gel and 1200# hulls.
Max. P.S.I. 500#. S.I.P. 200#.
NOTE: Plugged down casing so we could slug with cotton seed hulls, without plugging tubing off.

2/5/01 RECEIVED
STATE CORPORATION COMMISSION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

JAN 30 2001

Invitation For Bid Number 02291
Page 35

BROADVIEW OIL CO #C-2 LIVINGOOD 11-9-16W
CWL SW NE

Contr. _____ ROOKS County

E. 2079 Comm. 1-21-41 Comp. 2-17-41 IP 75 BOPD

Tops	Depth	Datum	Casing
ANH	1320		5" 3247
TOP	2947		A/8000
LANS	3224		
TD	3258		

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

