

To: 6 040981
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

~~X~~ 10-21 no c
→
API NUMBER 15-8290 15-163-03749-00-01

N/2 SW , SEC. 11, T 9 S, R 16 W ~~SE~~
330 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5769

Lease Name Tatkanhorst Well # C-1 SWD

Operator: Harold Kruger Co.

County Rooks 104.33

Name & Address Natoma, Ks. 67651

Well Total Depth PB 1000 3210 feet

Conductor Pipe: Size feet

Surface Casing: Size 10" feet 90' w/100 sks

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cement License Number

Address Hays, Ks.

Company to plug at: Hour: 9:00 Day: 21 Month: Oct Year: 19 88

Plugging proposal received from Dean Wineland

(company name) Kruger Co. (phone)

were: 7" casing set at 3210' w/100 sks. Top perf at 765' - 875'. PB at 1000'

Base Dakota at 620'. Top cement at 325' to 875' w/425 sks. Halliburton Temp survey.

PB w/sq at 980' w/425. Perf at 315' w/circ w/135 sk cement. Ordered 250 sks

60/40 Poz 8% Cel w/1/4# F.C.

Plugging Proposal Received by Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 11:15AM Day: 21 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 7" casing 135 sks cement w/1/4# F.C. mixed in
cement. Max 500#. S.I. 250# psi.

RECEIVED
STATE CORPORATION COMMISSION

12/29/88
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

I (or ~~we~~) authorize observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis L. Hamel

DATE 1-5-89

INV. NO. 23494