

To: 6 040832
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-18-87
API NUMBER 15-143-03750-00-28⁰¹
NE SE SW, SEC. 11, T 9 S, R 16 W/E

990 feet from S section line
3630 feet from E section line

Lease Name Tatkenhorst Well # 2 SWD

County Rooks 106.99

Well Total Depth 3292 feet

Conductor Pipe: Size feet

Surface Casing: Size feet

TECHNICIAN'S PLUGGING REPORT

Operator License # 5769

Operator: Harold Kruger Co.

Name & Address

Natoma, Ks. 67651

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cmt. License Number

Address Hays, Kansas

Company to plug at: Hour: Day: Month: 12 Year: 19 87

Plugging proposal received from Dean Wineland

(company name) Harold Kruger Co. (phone)

were: 7" casg. set at 3290' w/ cmt. N.A. C.I.B.P. at 3070' Perf. at 3100'-3290'

Perf. anhydrite at 1250'; Perf. Dakota at 700'

Ordered 400 sx 65/35 poz. 10% gel w/ 1/2 # flocele w/ 12 sx hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:00PM Day: 18 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT

Pumped in 7" casg : 50 sx cmt. w/ 1/2 # flocele, plus 250 sx w/ 8 sx hulls Max. 900 #

P.S.I. : Perf csg at 110', Pmped 100 sx cmt circ cmt to surf. El. 2070

Top Fluid at 1500' before perf.

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1988 1/18/88

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-20-88

DIV. NO. 19603

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis Hamel