

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03751-00-00
Spot: N2NWSW Sec/Twnshp/Rge: 11-9S-16W
2310 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: TATKENHORST C Well Number: 3
County: ROOKS Total Vertical Depth: 3181 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

Production Casing Size: 7 feet: 3160
Surface Casing Size: 10 feet: 18

103.38

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/03/2003 1:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered out 470 sxs 60/40 pozmix - 10% gel - 500# hulls - 12 sxs gel.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 07/16/2003 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

07-03-2003
Perforated casing at 550' - 1280' - 1700'.
Swaged onto 7" - mixed and pumped 65 sxs cement with 400# hulls, followed by 12 sxs gel and topped with 405 sxs cement.
S.I.P. 50#.
07-16-2003 - Tied onto 7" and circulated up annulus with 85 sxs cement.

RECEIVED
JUL 21 2003
KCC WICHITA

7/21/03

Remarks: COPELAND ACID & CEMENTING.

Plugged through: CSG

District: 04

Signed _____

Jay Pfeifer
(TECHNICIAN)

160
INVOICED
DATE 7-23-03
INV. NO. 2004060087

JUL 17 2003

KRUEGER OIL CO

#G-3 TATKENHORST

11-9-16W

CNL NW SW

Contr.

BOOKS County

E 2012

Comm. 5-1-40

Comp. 5-19-40

IP

486 BOPD

Tops	Depth	Datum
ANH	1272	
LANS	3160	
TD	3181	

Casing
 10" 18
 7" 3160
 SO 3163-81
 A/2000
 800' OIH
 Pmp 240 BO/16 hrs

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS