

15-163-03852-20-001

6 040841

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Operator: Murfin Drilling Co.

Name & Address Box 130

Hill City, Ks. 67642

Abandoned Oil Well Gas Well

Other well as hereinafter indicated

Plugging Contractor Allied Cementing

Address Russell, Ks.

Company to plug at: Hour: AM Day: 12 Month: Jan Year: 19 88

Plugging proposal received from John Neurnberger

(company name) Murfin Drilling Co. (phone #) 013-674-2103

were: 5 $\frac{1}{2}$ " casing at 3226' w/125 sks cement. Open hole 3236' - 3305'; Casing perf atAnhy and circ cement to surface; Tubing fish at 1100'. Ran W.L.M. to 455'. Perf casing at 450'. Ordered 250 sks 65/35 Poz 10% Gel 2% Lite w/ $\frac{1}{4}$ # plus 5 sks Hulls.Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00PM Day: 12 Month: Jan Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 $\frac{1}{2}$ " casing 100 sks cement w/ $\frac{1}{4}$ # Flocole followed w/ 150 sks cement w/5 sks Hulls. Max 800# Shut in 500#.

1/25/88

1/25/88

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-26-88

INV. NO. 19671

1-12-88

API NUMBER 15- 8 - 40 E-11,184

C S/2 NE, SEC. 11, T 9 S, R 16 (W/E)

feet from S section line

feet from E section line

Lease Name Livingood Well # 4 SWD

County Rooks

107.4

Well Total Depth 3305 feet

Conductor Pipe: Size feet

Surface Casing: Size 10" feet 25' cmt NA

Input Well X SWD Well X D&A

KCC

X

X D&A

X

X D&A