

15-163-03991-08-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- _____

C12-NE-SW Sec. 11, T 9 S, R 16 (W)E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5769

Lease Name Tatkeblood Well # 'C'-2

Operator: Harold Kruger Co.
Name &
Address P.O. Box 247
Natoma, ks 67651

County Rooks

Well Total Depth 3230 feet \$104.98

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 1 1/2 feet _____

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Conty License Number _____

Address Stays, Kansas

Company to plug at: Hour: 1:00 PM Day: 4 Month: 5 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Dean Winland

(company name) Kruger (phone) _____

were: 7" set @ 3281' w/100 sx - 5" line from 3188-3165

31 jts they pulled out - conty & they in hole @ 1140

Run flights 1135' - Ordered 580 sx 20 pgs 42 cc 60 gel

& 8 hulls. Pumped into esg. 50 sx cont only then 200 sx

w/ hulls & pumpd w plug to 850' - Wait 4 hrs - Pressure

to 300# - no movement

Signed Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:00 PM Day: 4 Month: 5 Year: 19 83

ACTUAL PLUGGING REPORT Cont. from above

Ref @ 750' - pressure up to 500# - no movement

" " 550' pressure up to 500# - no movement

" " 350' pressure to 500# @ 1/2 bbl per min - pumped

50 sx cont only - then 200 sx cont w/ hulls cont use

to surface. Shut in P.S.I. 250#

Remarks: Operator stated well had been squeezed
several times

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 6-24-83

INV. NO. 4662-W

Signed Dennis L. Hamel
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

FORM CP-2/3
Rev. 9-82

JUN 17 1983

CONSERVATION DIVISION
Wichita, Kansas

6/17/83

250#
Pumping
P.S.I.