

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19012-00-00
Spot: CW2NE Sec/Twnshp/Rge: 11-9S-16W
3960 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: LIVINGOOD C Well Number: 3
County: ROOKS Total Vertical Depth: 3440 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 251
Production: Size 4.5 feet: 3439
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2001 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Cleaned out bridges to 1580'. Iron in hole, unable to clean out.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/23/2001 1:15 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated at 1580' - 1320' - 760'.
Ran tubing to 1550'. Allied pumped 65 sxs 60/40 pozmix - 10% gel with 200# hulls. Cement circulated.
PTOH. Allied squeezed 135 sxs with 200# hulls.
Max. P.S.I. 600#. S.I.P. 200#.
Backside pumped 50 sxs with 100#hulls.
Max. P.S.I. 500#. S.I.P. 300#.

2/5/01
RECEIVED
STATE CORPORATION COMMISSION
FEB 01 2001

Remarks: ALLIED CEMENTING COMPANY

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

FEB 01 2001

BROADVIEW OIL

#3-C LIVINGOOD

20 11-9-16W
C W2 NE

Contr. SHIELDS OIL

ROOKS

County

E 2082 RB Comm 5-21-62

Comp. 6-21-62

IP 20 BOPD, NW, GR 41/

LAN5 3241-3390

Log Tops	Depth	Datum
TOP	2956	-874
HEEB	3180	-1098
TOR	3199	-1117
LAN5	3219	-1137
TD	3440	-1358

Casing

8" 251

5" 3439

NO TESTS

CO 3410: PERF 19/3241-47: 8/

3260-64: 22/3273-80: 25/3324-

32: 32/3362-74: 14/3384-90:

ACID 10,000: SWB 3 BOPH/4 HRS
NW

LATON POOL

JAMES DANIEL, SR.
GEOL.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS