

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Commercial Oil Company,

Complete Address: 5252 North Broadway, Wichita, Kansas.

Lease Name: Pratt Well No. 7

Location: CNW-NW-SW Sec. 23 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3865' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

262'--10 3/4" Surface casing cement circulated with 260 Sx.
3843'--7" OD Production casing cemented on bottom with 200 Sx. No plug back nor perforations indicated.

Push plug to 3625', sand back from 3625' to 3600' and set 6 Sx. cement with dump bailer. Pull 7" casing and squeeze well with 6 sacks hulls, 40 sacks gel and 180 Sx. cement, staged.

Very truly yours,

K. L. Nichols
Conservation Division Agent