

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1967
07-12-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-179-20025-00-00

Dear Sir:

Mr. Marion Helberg of Helberg Oil Company, has this date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Helberg Oil Company

Complete Address: Box # 32, Morland, Kansas.

Lease Name: Dallis Jones Well No. 1

Location: SW-SE-SE Sec. 24 Twp. 8 Rge. (E)(W) 26

County Sheridan Total Depth 4020 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

- 118'--8 5/8" Surface pipe, cement circulated.
- Circulate hole with heavy mud, set plug @ 625' and 20 Sx. cement.
- " " 150' with 1/4 sk. hulls & 20 Sx. cement.
- " " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

A. L. Nichols

Conservation Division Agent