



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-179-0 0104-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1972
CONSERVATION DIVISION
Wichita, Kansas

03-27-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: Box #352, Russell, Kansas.

Lease Name: Pratt Well No. A-1

Location: SE-SE-NE Sec. 26 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3940' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

160'--8 5/8" Surface casing, cement circulated.

3913'--5 1/2" Production casing cemented on bottom with 125 Sx. No plug-back indicated. Top of perforations @ 3703'.

Push plug to 3675', sand back to 3650 and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent