



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

15-179-20652-00-00

Mr. Harold Maley of Abercrombie Drlg., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Tenneco Oil Co.

Complete Address: 139 Ciudad Bldg. 3000 United Founders Bldg., Oklahoma, City, Ok. 73112

Lease Name: Mader Well No. 1-26

Location: 2010' FNL - 310' FWL Sec. 26 Twp. 8 Rge. 26 (E) (W)

County: Sheridan Total Depth: 3960'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Maley was instructed to plug the well as follows:

8 5/8"-280' S.P. cuc w/190 sacks common-2% Gel.-3% Cal.Cl.

Ordered 140 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 1120' w/80 sacks cement

2nd plug @ 300' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Very truly yours,

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
AUG 02 1982
08-02-1982
CONSERVATION DIVISION
Wichita, Kansas