

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
APR 3 1967  
4-3-1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Three G Oil, Incorporated,

Complete Address: 1101 Wichita Plaza, Wichita, Kansas.

Lease Name: Farber Trustee Lease Well No. 1

Location: NW-NE-SW Sec 27 Twp. 8 Rge. (E)(W) 26

County Sheridan Total Depth 3955 Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Norwood was instructed to plug the well as follows:

290' -- 8 5/8" Surface pipe, cement circulated with 185 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

" " 280' with 1/4 sk. hulls & 20 Sx. cement.  
" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

M. L. Nichols  
Conservation Division Agent