

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
12-10-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Company,

Complete Address: 603 Union Center, Wichita, Kansas.

Lease Name: Pratt Estate Well No. 1

Location: SW-SW-NW Sec. 22 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3860' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

259'--8 5/8" Surface casing, cement circulated with 180 Sx.  
Top of Dakota section @ 925'.

Circulate hole with heavy mud. Pull DP to 1150' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. J. Nichols  
Conservation Division Agent