

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 22 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 1-22-1969

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Lowell Moore of C & G Drilling Company, has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen Trust,

Complete Address: Box #187, Logan, Kansas.

Lease Name: Hansen Fee Well No. D-5

Location: SE-SE-NW Sec. 28 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3935 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

201'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

N. L. Nichols  
 Conservation Division Agent